



Minimum 30ft x 30ft Crane Pad, within 18in of level. Stone required if wet or soft. K-Wall is not responsible for cleaning of roadway

Minimum 16ft wide, fairly level driveway with road bond stone placed. Entrance needs to be wide for large turning radius of equipment

3ft over-dig between wall lines & banks

Do Not Pre-Dig Garage Area. It Will Cause Loss Of Reach For Crane

6in minimum of 78A stone base, at least 3' wider than perimeter of MonoKast Walls

Signature/Date: